


SEC 9 T2W R15E




LEGEND:

- = 3/4" x 24" SOLID ROUND #6 IRON REBAR SET
- = 3/4" IRON REBAR FOUND
- ⊕ = BERTSEN MONUMENT
- = P.K. NAIL

EAST 1/4 CORNER OF
SECTION 9-20-15

NORTHEAST CORNER
SECTION 9-20-15

DESCRIPTION: A PARCEL OF LAND LOCATED IN THE NE1/4 OF THE NE1/4 OF SECTION 9, T20N, R15E, TOWN OF WINCHESTER, WINNEBAGO COUNTY, WISCONSIN, MORE FULLY DESCRIBED AS FOLLOWS: COMMENCING AT THE NORTHEAST CORNER OF SECTION 9; THENCE S00°-11'-32"W, 1784.92 FEET ALONG THE EAST LINE OF THE NE1/4 OF SECTION 9 TO THE NORTHEASTERLY RIGHT OF WAY LINE OF C.T.H. "W"; THENCE N36°-09'W, 1709.26 FEET ALONG SAID RIGHT OF WAY TO THE POINT OF BEGINNING; THENCE CONTINUING N36°-09'W, 143.00 FEET ALONG SAID RIGHT OF WAY TO THE SOUTHERLY LINE OF LOT ONE OF CERTIFIED SURVEY MAP NO. 1801; THENCE N84°-42'-31"E, 176.88 FEET ALONG SAID SOUTHERLY LINE TO THE WESTERLY LINE OF SAID CERTIFIED SURVEY MAP; THENCE S08°-24'-40"E, 91.01 FEET ALONG SAID WESTERLY LINE; THENCE S88°-43'-53"W, 42.00 FEET; THENCE S57°-06'-03"W, 75.15 FEET TO THE POINT OF BEGINNING. SAID PARCEL CONTAINS 0.345 ACRES OF LAND MORE OR LESS. SUBJECT TO ALL EASEMENTS AND RESTRICTIONS OF RECORD. THIS PARCEL TO BE SOLD TO ADJACENT LAND OWNER.



Michael D. Vander Bloomen 10-17-88

I, MICHAEL D. VANDER BLOOMEN, CERTIFY THAT THIS PLAT OF SURVEY IS A CORRECT REPRESENTATION OF THE ABOVE DESCRIBED PROPERTY.

REVISIONS	MELVIN SELLE BOX 204 SHIOCTON, WISCONSIN 54170		
	CAROW LAND SURVEYING CO., INC., P.O. BOX 1297 1837 W. WISCONSIN AVE. • APPLETON, WI 54912		
DRAWN BY	MV-dv MV	SCALE	1"=60'
DATE	10-17-88	DRAWING NO.	A8711.42-88
APPROD	X		

693990

Register's Office

Winnebago County, Wis.

Received for record this 28th
day of Dec. A.D., 1987
at 1:30 o'clock P.M. and
recorded in Vol. 1 of CSM
on page 1801.

Gregorio Dahmed


Register of Deeds

Lathrop & Johnson Pds
Hartsville 6⁰²

Stock No. 26273

CERTIFIED SURVEY MAP NO. 1801

A PARCEL OF LAND LOCATED IN THE NE $\frac{1}{4}$ OF THE NE $\frac{1}{4}$ OF SECTION 9, T20N, R15E, TOWN OF WINCHESTER, WINNEBAGO COUNTY, WISCONSIN.



Stack No. 26273

CERTIFIED SURVEY MAP NO. 1801


SURVEYOR'S CERTIFICATE:

I, MICHAEL D. VANDER BLOOMEN, REGISTERED WISCONSIN LAND SURVEYOR, CERTIFY THAT I HAVE SURVEYED, DIVIDED AND MAPPED PART OF THE NE $\frac{1}{4}$ OF THE NE $\frac{1}{4}$ OF SECTION 9, T20N, R15E, TOWN OF WINCHESTER, WINNEBAGO COUNTY, WISCONSIN, BOUNDED AND DESCRIBED AS FOLLOWS: COMMENCING AT THE NORTHEAST CORNER OF SECTION 9; THENCE S00°-11'-32"W, 1784.92 FEET ALONG THE EAST LINE OF THE NE $\frac{1}{4}$ OF SECTION 9 TO THE NORTHEASTERLY RIGHT OF WAY LINE OF O.T.H. W; THENCE N36°-09'-00"W, 1852.26 FEET ALONG SAID NORTHEASTERLY LINE TO THE POINT OF BEGINNING; THENCE CONTINUING N36°-09'-00"W, 40.00 FEET ALONG SAID NORTHEASTERLY LINE; THENCE N83°-01'-54"E, 214.33 FEET; THENCE N43°-57'-45"E, 124.41 FEET; THENCE N5°-28'-08"E, 122.63 FEET; THENCE N89°-00'-20"E, 14.67 FEET; THENCE S00°-07'-56"W, 101.40 FEET; THENCE S29°-34'-24"E, 117.33 FEET; THENCE S11°-30'-25"E, 148.90 FEET; THENCE N88°-43'-53"W, 199.80 FEET; THENCE N8°-24'-40"W, 91.01 FEET; THENCE S84°-42'-31"W, 176.88 FEET TO THE POINT OF BEGINNING. SAID PARCEL OF LAND CONTAINS 1.04 ACRES OF LAND MORE OR LESS.

THAT I HAVE MADE SUCH SURVEY UNDER THE DIRECTION OF MARVIN SELLE, 9292 O.T.H. W, LARSEN, WISCONSIN. 54947

THAT THIS MAP IS A CORRECT REPRESENTATION OF THE EXTERIOR BOUNDARY LINES OF THE LAND SURVEYED.

THAT I HAVE FULLY COMPLIED WITH THE PROVISIONS OF CHAPTER 236.34 OF THE WISCONSIN STATUTES AND THE SUBDIVISION REGULATIONS OF WINNEBAGO COUNTY.



Michael D. Vander Bloomen 11-16-87
MICHAEL D. VANDER BLOOMEN, RLS-1828 DATED
CAROW LAND SURVEYING CO., INC.
1837 W. WISCONSIN AVE. P.O. BOX 1297
APPLETON, WISCONSIN 54912-1297

OWNER'S CERTIFICATE:

AS OWNERS WE HEREBY CERTIFY THAT WE CAUSED THE LAND DESCRIBED ON THIS CERTIFIED SURVEY MAP TO BE SURVEYED, DIVIDED AND MAPPED AS REPRESENTED. WE ALSO CERTIFY THAT THIS MAP IS REQUIRED BY S.236.10 OR S.236.12 OF THE WISCONSIN STATUTES TO BE SUBMITTED TO THE FOLLOWING FOR APPROVAL, WINNEBAGO COUNTY PLANNING AND ZONING COMMITTEE.

WITNESS THE HAND AND SEAL OF SAID OWNER'S THIS 8th DAY OF December, 1987.
IN THE PRESENCE OF:

Melvin L. Selle
OWNER Melvin L. Selle

Corinne Kateau
WITNESS Corinne Kateau

Marvin G. Selle
OWNER Marvin G. Selle

STATE OF WISCONSIN
COUNTY OF WINNEBAGO ss

PERSONALLY CAME BEFORE ME THIS 8th DAY OF December, 1987; THE ABOVE SIGNED PERSONS TO ME KNOWN TO BE THE PERSONS WHO EXECUTED THE FOREGOING INSTRUMENT AND ACKNOWLEDGED THE SAME.

Kelland W. Patch
NOTARY PUBLIC, WINNEBAGO COUNTY
MY COMMISSION EXPIRES: 1s Permanent

PURSUANT TO THE WINNEBAGO COUNTY SUBDIVISION ORDINANCE, ALL REQUIREMENTS FOR APPROVAL HAVE BEEN FULFILLED. THIS CERTIFIED SURVEY MAP WAS APPROVED ON THE 28th DAY OF December, 1987.

Jeanette Diakoff
V. CHAIRMAN, WINNEBAGO COUNTY
PLANNING AND ZONING COMMITTEE

NORTH LINE OF THE
SE $\frac{1}{4}$ OF SEC. 9

S89°-31'-44"W

957.00'

EAST $\frac{1}{4}$ CORNER OF
SECTION 9-20-15


DESCRIPTION: A PARCEL OF LAND LOCATED IN THE NE $\frac{1}{4}$ OF THE SE $\frac{1}{4}$ OF SECTION 9, T20N, R15E, TOWN OF WINCHESTER, WINNEBAGO COUNTY, WISCONSIN. COMMENCING AT THE EAST $\frac{1}{4}$ CORNER OF SECTION 9; THENCE S89°-31'-44"W, 957.00 FEET ALONG THE NORTH LINE OF THE SE $\frac{1}{4}$ OF SECTION 9 TO THE CENTERLINE OF A ROAD; THENCE S10°-46'W, 78.00 FEET (RECORDED AS 70.00 FEET) ALONG SAID CENTERLINE TO THE POINT OF BEGINNING; THENCE CONTINUING S10°-46'W, 600.00 FEET ALONG SAID CENTERLINE; THENCE S89°-31'-44"W, 145.20 FEET; THENCE N10°-46'E, 600.00 FEET; THENCE N89°-31'-44"E, 145.20 FEET TO THE POINT OF BEGINNING. SAID PARCEL CONTAINS 2.00 ACRES OF LAND MORE OR LESS. SUBJECT TO ALL EASEMENTS AND RESTRICTIONS OF RECORD. RESERVING THAT PART PRESENTLY USED FOR ROAD PURPOSES.

LEGEND

⊙ = HERNTSEN MONUMENT FOUND

• = 3/4" x 24" SOLID ROUND #6 REBAR SET


■ = P.K. NAIL SET



I, ROBERT F. REIDER, CERTIFY THAT THIS PLAT OF SURVEY IS A CORRECT REPRESENTATION OF THE PROPERTY DESCRIBED.

Robert F. Reider 3-9-83


THERE ARE NO ENCROACHMENTS.
HOUSE IS A TWO STORY WITH ATTACHED GARAGE.



REVISIONS	CENTURY 21 c/o JERRY MC ANULTY P.O. BOX 447, APPLETON, WIS. 54912		
	CAROW LAND SURVEYING CO., INC., P.O. BOX 1297 1837 W. WISCONSIN AVE. • APPLETON, WI 54912		
	DRAWN BY RFR	SCALE 1"=100'	DRAWING NO.
	APPD LEC	DATE 3-9-83	A833.43

Survey for Art Linsedt:

Survey of that part of the North East 1/4 of the South East 1/4 of Section 9 Township 20 North of Range 15 East in the Town of Winchester, Winnebago County, Wisconsin bounded and described as follows: Commencing at the East 1/4 Post of said section 9, thence West along the East and West 1/4 line 957.0 feet, to the center line of a road running North and South, thence South along the center line of said road 70.0 feet to the place of beginning, thence continuing South along the center line of said road 600.0 feet, thence West parallel with the East and West 1/4 line 145.2 feet, thence North parallel with the center line of said road 600.0 feet, thence East and parallel with the East and West 1/4 line 145.2 feet to the place of beginning, containing 2.0 acres.



SURVEY & ENGINEERING CO. & P.

Oshkosh, Wis.

T. R. STEARNS, SURVEYOR

Date May 22, 1958

Job # B-24.



CERTIFIED SURVEY MAP NO. 3797

BEING ALL OF LANDS DESCRIBED IN DOCUMENT NUMBER 643206, BEING PART OF THE SOUTHEAST 1/4 OF THE NORTHEAST 1/4 OF SECTION 9, TOWNSHIP 20 NORTH, RANGE 15 EAST, TOWN OF WINCHESTER, WINNEBAGO COUNTY, WISCONSIN.

NORTHEAST CORNER
SECTION 9, T20N,
R15E


NORTH IS REFERENCED TO THE EAST LINE
OF THE NORTHEAST 1/4 OF SECTION 9,
T20N, R15E, TOWN OF WINCHESTER,
WINNEBAGO COUNTY, WISCONSIN, WHICH
IS ASSUMED TO BEAR $N00^{\circ}-11'-32''E$.

UNPLATTED LANDS

NORTH LINE OF THE SE 1/4
OF THE NE 1/4 OF SECTION 9

30' INGRESS & EGRESS
EASEMENT

LANDS DESCRIBED IN DOC. # 716929




NOTE: BEING ALL OF TAX PARCEL
NUMBER 028-0266-01

LANDS DESCRIBED IN
DOC. # 716929

SETBACKS

STREET	-	75 FEET	MIN.
REARYARD	-	50 FEET	MIN.
SIDEYARD	-	15 FEET	MIN.



CHRISTOPHER E. PERREAULT RLS 2249 DATE
CAROW LANDSURVEYING CO., INC.
1837 W. WISCONSIN AVE., P.O. BOX 1297
APPLETON, WISCONSIN 54912-1297
(A8511.121-97 op ac CP (9-9-97))



CERTIFIED SURVEY MAP NO. 3797

BEING ALL OF LANDS DESCRIBED IN DOCUMENT NUMBER 643206, BEING PART OF THE SOUTHEAST 1/4 OF THE NORTHEAST 1/4 OF SECTION 9, TOWNSHIP 20 NORTH, RANGE 15 EAST, TOWN OF WINCHESTER, WINNEBAGO COUNTY, WISCONSIN.

NORTHEAST CORNER
SECTION 9, T20N,
R15E

NORTH IS REFERENCED TO THE EAST LINE
OF THE NORTHEAST 1/4 OF SECTION 9,
T20N, R15E, TOWN OF WINCHESTER,
WINNEBAGO COUNTY, WISCONSIN, WHICH
IS ASSUMED TO BEAR $N00^{\circ}-11'-32''E$.

UNPLATTED LANDS


NORTH LINE OF THE SE 1/4
OF THE NE 1/4 OF SECTION 9
30' INGRESS & EGRESS
EASEMENT

UNPLATTED
LANDS
DESCRIBED IN DOC. # 716929

LEGEND

- = 3/4" SOLID ROUND IRON REBAR FOUND
- = 3/4"x24" SOLID ROUND IRON REBAR SET WEIGHING 1.502 LBS. PER LN. FT.
- ⊙ = BERTSEN MONUMENT
- () = RECORDED AS DIMENSION

BAR-L-RANCH
LANE (495)





NOTE: BEING ALL OF TAX PARCEL
NUMBER 028-0266-01

LANDS DESCRIBED IN
DOC. # 716929

SETBACKS

STREET	-	75 FEET	MIN.
REARYARD	-	50 FEET	MIN.
SIDEYARD	-	15 FEET	MIN.



CHRISTOPHER E. PERREAULT RLS 2249 DATE
CAROW LANDSURVEYING CO., INC.
1837 W. WISCONSIN AVE., P.O. BOX 1297
APPLETON, WISCONSIN 54912-1297
(A8511.121-97 cp ac CP (9-9-97))

9-9-97



CERTIFIED SURVEY MAP NO. 3797


SURVEYOR'S CERTIFICATE:

I, CHRISTOPHER E. PERREAULT, REGISTERED WISCONSIN LAND SURVEYOR, CERTIFY THAT I HAVE SURVEYED, DIVIDED AND MAPPED PART OF THE SOUTHEAST 1/4 OF THE NORTHEAST 1/4 OF SECTION 9, TOWNSHIP 20 NORTH, RANGE 15 EAST, TOWN OF WINCHESTER, WINNEBAGO COUNTY, WISCONSIN, BOUNDED AND DESCRIBED AS FOLLOWS: COMMENCING AT THE EAST 1/4 CORNER OF SAID SECTION 9; THENCE N00-11-32E, 656.50 FEET ALONG THE EAST LINE OF THE NORTHEAST 1/4 OF SAID SECTION 9 TO THE SOUTH LINE OF THE NORTH 1/2 OF THE SOUTHEAST 1/4 OF THE NORTHEAST 1/4 OF SAID SECTION 9; THENCE S89-37-37W, 93.00 FEET ALONG SAID SOUTH LINE TO THE POINT OF BEGINNING; THENCE CONTINUING S89-37-37W, 549.77 FEET ALONG SAID SOUTH LINE; THENCE N49-44-42W, 232.71 FEET; THENCE N72-44-42W, 202.33 FEET; THENCE N25-35-18E, 258.77 FEET; THENCE N00-24-42W, 210.41 FEET (RECORDED AS 210.50 FEET) TO THE NORTH LINE OF THE SOUTHEAST 1/4 OF THE NORTHEAST 1/4 OF SAID SECTION 9; THENCE N89-35-18E, 462.35 FEET ALONG SAID NORTH LINE TO THE SOUTHWESTERLY RIGHT-OF-WAY LINE OF C.T.H. "W"; THENCE S36-09-00E, 590.91 FEET ALONG SAID SOUTHWESTERLY RIGHT-OF-WAY LINE; THENCE S00-11-32W, 176.78 FEET (RECORDED AS 176.87 FEET) TO THE POINT OF BEGINNING.

THAT I HAVE MADE SUCH SURVEY UNDER THE DIRECTION OF HUBERT PORSCHE, N9553 PLEASANT HILL ROAD, IOLA, WI. 54945.

THAT THIS MAP IS A CORRECT REPRESENTATION OF THE EXTERIOR BOUNDARY LINES OF THE LAND SURVEYED.

THAT I HAVE FULLY COMPLIED WITH THE PROVISIONS OF CHAPTER 236.34 OF THE WISCONSIN STATUTES AND THE SUBDIVISION ORDINANCE OF WINNEBAGO COUNTY.



Christopher E. Perreault 9-9-97
 CHRISTOPHER E. PERREAULT, RLS 1251 DATED
 CAROW LAND SURVEYING CO., INC.
 1837 W. WISCONSIN AVE, P.O. BOX 1297
 APPLETON, WI. 54912-1297
 A8511.121-97 (cp-ac CEP) 9-9-97

NOTES:

- 1) THE PROPERTY OWNER(S) OF RECORD IS(ARE): STEVEN A. & PAULA J. BASLER.
- 2) THIS CSM IS ALL OF TAX PARCEL NO. 028-0266-01.
- 3) THIS CSM IS CONTAINED WHOLLY WITHIN THE PROPERTY DESCRIBED IN THE FOLLOWING RECORDED INSTRUMENT(S): DOCUMENT NO. 643206

COUNTY PLANNING AND ZONING COMMITTEE APPROVAL:

PURSUANT TO THE WINNEBAGO COUNTY SUBDIVISION ORDINANCE, ALL REQUIREMENTS FOR APPROVAL HAVE BEEN FULFILLED. THIS CERTIFIED SURVEY MAP WAS APPROVED THIS 19th DAY OF September, 1996.

Joanne M. Suwert
 CHAIRPERSON, WINNEBAGO COUNTY PLANNING AND ZONING COMMITTEE

OWNER'S CERTIFICATE:

WITNESS THE HAND AND SEAL OF SAID OWNER(S) THIS 15 DAY OF SEP 1997.

Paula J. Basler
PAULA J. BASLER

PERSONALLY CAME BEFORE ME THIS 15 DAY OF Sept, 1997, THE ABOVE NAMED PERSON(S) TO ME KNOWN TO BE THE PERSON(S) WHO EXECUTED THE FOREGOING INSTRUMENT AND ACKNOWLEDGED THE SAME.

MY COMMISSION EXPIRES Jan. 25 1998

TREASURER'S CERTIFICATE:

I HEREBY CERTIFY THAT THERE ARE NO UNPAID TAXES OR UNPAID SPECIAL ASSESSMENTS ON ANY OF THE LAND INCLUDED ON THIS CERTIFIED SURVEY MAP.

Betty Nelson 9-15-97 Burton Schmidt 9/16/97
TOWN TREASURER DATED COUNTY TREASURER DATED



CHRISTOPHER E. PERREAULT, RLS-1251 DATED
CAROW LAND SURVEYING CO., INC.
1837 W. WISCONSIN AVE., P.O. BOX 1297
APPLETON, WISCONSIN 54912-1297
A8511.121-97 (cp ac CEP) 9-9-97

983048

SHEET 3 OF 3 SHEETS

Register's Office
Winnebago County, Wis.
Received for record this 19th
day of September, 1997
at 3:38 o'clock P.M. and
filed in Vol. 1 of CSM
on page 3297

Susan Wamagishi
Register of Deeds

Chg: Carson

AFFIDAVIT

1003294

REGISTER'S OFFICE
WINNEBAGO COUNTY, WI
RECORDED ON

1998-04-02 10:11 AM

SUSAN WINNINGHOFF
REGISTER OF DEEDS

Rec. Fee: 10.00
Tran. Fee: 0.00
Number of Pages: 1

S 9
T 20
R 15

STATE OF WISCONSIN)
COUNTY OF WINNEBAGO)SS

AFFIDAVIT OF CORRECTION

Return to:

Carow Land Surveying
P.O. Box 1297
Appleton, WI 54912-1297
A8511.121-97

I, CHRISTOPHER E. PERREAULT, Registered Land Surveyor No. S-2249, of the State of Wisconsin, do hereby depose and say:


That I have surveyed, divided and mapped Winnebago County Certified Survey Map No. 3797 as recorded in Volume 1 of Certified Survey Maps on page 3797, being Document No. 983048.

That on the first page of said map, I included the right-of-way of Bar-L-Ranch Lane as part of Lot 1, when in fact Bar-L-Ranch Lane was previously dedicated and should not have been included with Lot 1. That also on the first page of said map, I show the total square footage of Lot 1 as "379,953" and usable as "363,618", when in fact I should have shown the square footage of Lot 1 as "363,618".

That on the first page of said map, I show "sheet 1 of 2 sheets", when in fact I should have shown "SHEET 1 OF 3 SHEETS".

That this affidavit is given for the purpose of correcting said Certified Survey Map and for no other purpose.

Dated this 31st day of March, 1998.
In the presence of:




CHRISTOPHER E. PERREAULT

STATE OF WISCONSIN)
COUNTY OF WINNEBAGO)SS

Personally came before me this 31st day of March, 1998, the above named Christopher E. Perreault, to me known to be the person who executed the foregoing instrument and acknowledged the same.



Notary Public, Winnebago County, WI
My commission expires: 1-7-2001



This instrument drafted by David G. Verhagen

Plat of Survey

Being a part of the NE 1/4 of the SE 1/4 of Section 9, T.20N., R.15E., Town of Winchester, Winnebago County, Wisconsin, containing 36.100 Acres of land m/l and being described by:
Commencing at the E 1/4 corner of said Section 9; thence S.89°39'57"W. 66.00', along the North line of the NE 1/4 of the SE 1/4 of the true point of beginning;
thence S.00°10'55"W. 1314.40', parallel to the East line of the NE 1/4 of the SE 1/4 of said Section 9, to the South line of the NE 1/4 of the SE 1/4 of said Section 9;
thence S.89°36'15"W. 1262.78', along the South line of the NE 1/4 of the SE 1/4 of said Section 9, to the SW corner of the NE 1/4 of the SE 1/4 of said Section 9;
thence N.00°15'02"E. 1315.77', along the West line of the NE 1/4 of the SE 1/4 of said Section 9, to the NW corner of the NE 1/4 of the SE 1/4 of said Section 9;
thence N.89°39'57"E. 1261.19', along the North line of the NE 1/4 of the SE 1/4 of said Section 9 to the true point of beginning. Subject to all easements and restrictions of record. Reserving that part presently used for road purposes.

Less and excepting a parcel of land located in the NE 1/4 of the SE 1/4 of said Section 9, containing 2.0 acres of land m/l and being described by commencing at the E 1/4 corner of said Section 9; thence S.89°39'57"W. 957.35', (recorded as S.89°31'44"W. 957.00'), along the North line of the NE 1/4 of the SE 1/4 of said Section 9; thence S.01°46'49"W. 73.75', along the centerline of a road, (recorded as S.01°46'W. 78.00'), to the true point of beginning; thence continue S.01°46'49"W. 600.00', along the centerline of said road, (recorded as S.01°46'W. 600.00'); thence S.89°33'35"W. 145.15' (recorded as S.89°31'44"W. 145.2'); thence N.01°46'49"E. 600.00', (recorded as N.01°46'E. 600.00'); thence N.89°33'35"E. 145.15', (recorded as N.89°31'44"E. 145.2'), to the true point of beginning.



Surveyor's Certificate

I, Thomas M. Kromm, Wisconsin Registered Land Surveyor of Kromm Land Surveying, certify that I have surveyed the above described property and that the map shown is a true and accurate representation thereof to the best of my knowledge and belief. Kromm Land Surveying has made no investigation or independent search for easements of record, encumbrances, restrictive covenants, or any other facts that an accurate and current title search may disclose. This Survey is valid only if print has original seal and signature.



Dated this 2nd day of February, 2000

Thomas M. Kromm
Wisconsin Registered Land Surveyor
Thomas M. Kromm

SURVEY FOR: ED WALTERS




- LEGEND
- = 1" x 24" Iron pipe weighing 1.68 lbs/ft. set
 - = 1" Iron pipe found
 - = 3/4" Iron rebar found
 - = 1 1/4" Iron rebar found
 - ✕ = Pk nail set
 - ✕ = Pk nail found
 - () = Measurements of record




KROMM LAND SURVEYING
1284 Harold Drive
Menasha, WI 54952
K-1090

FOR: ED WALTERS




ALL BEARINGS REFERENCED TO THE EAST LINE
OF THE SW 1/4 OF SECTION 8, T.20N., R. 15E.
RECORDED TO BEAR N 00° 10' 55"E.



STATE OF WISCONSIN DEPT. OF NATURAL RESOURCES

KROMM LAND SURVEYING
1284 Harold Drive
Menasha, WI 54952
K-1090

- ### LEGEND
- = 1" x 24" iron pipe weighing 1 LB
lb/ft. set
 - = 1" iron pipe found
 - = 3/4" iron rebar found
 - = 1 1/4" iron rebar found
 - ⌘ = Pl. not set
 - ⌘ = Pl. not found
 - () = Measurements of record



Plat of Survey

SHEET 1 OF 1

Being all of the NW 1/4 of the SE 1/4 of Section 9, T.20N., R.15E., Town of Winchester, Winnebago County, Wisconsin, containing 40.133 Acres of land m/l and being described by:

Commencing at the E 1/4 corner of said Section 9; thence S.89°39'57"W. 1327.19', along the North line of the SE 1/4 of said Section 9, to the NE corner of the NW 1/4 of the SE 1/4, and being the true point of beginning;

thence S.00°15'02"W. 1315.77', along the East line of the NW 1/4 of the SE 1/4, to the SE corner of the NW 1/4 of the SE 1/4, of said Section 9;

thence S.89°36'15"W. 1328.79', along the South line of the NW 1/4 of the SE 1/4 of said Section 9, to the SW corner of the NW 1/4 of the SE 1/4, of said Section 9;

thence N.00°19'09"E. 1317.24', along the West line of the NW 1/4 of the SE 1/4, to the Center of said Section 9;

thence N.89°39'57"E. 1327.19', along the North line of the NW 1/4 of the SE 1/4 of said Section 9, to the true point of beginning. Subject to all easements and restrictions of record.

Surveyor's Certificate


I, Thomas M. Kromm, Wisconsin Registered Land Surveyor of Kromm Land Surveying, certify that I have surveyed the above described property and that the map shown is a true and accurate representation thereof to the best of my knowledge and belief. Kromm Land Surveying has made no investigation or independent search for easements, covenants, or any other facts that an accurate and current title search may disclose. This survey is valid only if printed on original soil and signature.

Dated this 2nd day of February, 2000

Thomas M. Kromm

Wisconsin Registered Land Surveyor
Thomas M. Kromm



SURVEY FOR: MIKE ROGERS



ALL BEARINGS REFERENCED TO THE EAST LINE OF THE SE 1/4 OF SECTION 9, T.20N., R.15E., RECORDED TO BEAR N.00°10'55"E.

LEGEND

- = 1" x 24" Iron pipe weighing 1.65 lbs/ft. set
- = 1" Iron pipe found
- = 3/4" Iron rebar found
- = 1 1/4" Iron rebar found
- ⊥ = Pk nail set
- ⊥ = Pk nail found
- () = Measurements of record



Plan of Survey

SHEET 1 OF 1

Being all of the NW 1/4 of the SE 1/4 of Section 9, T.20N., R.15E., Town of Waukena, Winnebago County, Wisconsin, containing 40.133 Acres of land in/ and being described by:

Commencing at the E 1/4 corner of said Section 9, thence S. 89° 39' 57" W. 1327.19', along the North line of the SE 1/4 of said Section 9, to the NE corner of the NW 1/4 of the SE 1/4, and being the true point of beginning.

thence S. 00° 15' 02" W. 1315.77', along the East line of the NW 1/4 of the SE 1/4, to the SE corner of the NW 1/4 of the SE 1/4 of said Section 9;

thence S. 89° 36' 15" W. 1328.79', along the South line of the NW 1/4 of the SE 1/4 of said Section 9, to the SW corner of the NW 1/4 of the SE 1/4, of said Section 9;

thence N. 00° 19' 09" E. 1317.24', along the West line of the NW 1/4 of the SE 1/4, to the Center of said Section 9;

thence N. 89° 39' 57" E. 1327.19', along the North line of the NW 1/4 of the SE 1/4 of said Section 9, to the true point of beginning. Subject to all easements and restrictions of record.

Surveyor's Certificate


I, Thomas M. Kromm, Wisconsin Registered Land Surveyor of Kromm Land Surveying, certify that I have surveyed the above described property and that the map shows an true and accurate representation thereof to the best of my knowledge and belief. Kromm Land Surveying has made an investigation or independent search for easements of record, encumbrances, restrictive covenants, or any other facts that an accurate and current title search may disclose. This Survey is valid only if print has original and not signature.

Dated this 7th day of February, 2000.

Thomas M. Kromm

Wisconsin Registered Land Surveyor
Thomas M. Kromm

SURVEY FOR: MIKE ROGERS



ALL BEARINGS REFERENCED TO THE EAST LINE OF THE SE 1/4 OF SECTION 9, T.20N., R.15E. RECORDED TO BOOK N.00° 10' 55" E.

LEGEND

- = 1" x 24" iron pipe weighing 1.65 lbs/ft. set
- = 1" iron pipe found
- = 3/4" iron rebar found
- = 1 1/4" iron rebar found
- ~ = Pk. nail set
- x = Pk. nail found
- () = Measurements of record

